

US 60 West & KY 801 SSO Correction Project

The project proposes capital improvements throughout sections of Morehead Utility Plant Board's (MUPB) collection system to correct capacity issues and sanitary sewer overflows (SSO). By installing new interceptors between lift stations and increasing the capacity and total dynamic head of several lift stations, the overall capacity in the area will increase and reduce the number of SSO events, the primary goal of this project. A total of 68,000 LF of force mains and gravity sewers will be installed to address the hydraulic bottleneck.

Bid Opening - August 14, 2019

Approximate start date – October 15, 2019

Approximate completion date – October 15, 2020

Stonecrest / Armory Sewer Extension

The project proposes to provide sewer and/or water services to new cooperative plant and 60-home subdivision located at Ben Lowe Road.

Approximate start date – September 2019

Approximate completion date November 2019

Tank Rehab

Morehead Utility Plant Board program to rehabilitate and maintain water tanks yearly.

MMRC Tank to be completed by end of summer 2019

Wilson/Knapp Tank to be completed by Fall 2019

Shawnee Estates - 801 N @ Rice Road

Providing sewer service to approximately 40 new homes.

Project currently in the planning process

AppHarvest

The project will provide water and sewer services to new agricultural industry located at KY 801 North.

Approximate start date – October 15, 2019

Approximate completion date – July 1, 2020